

Concrete Core Testing and Footing Depth Measurement



Wood Research and Development	Attention to:	Date of Quote
Omar Abdelkarim PO Box 3014 Hillsborough, NB E4H 2C1 1-877-353-0683 abdelkarimo@woodrandd.com	Bill Goulding City of Elliot Lake 45 Hillside Drive North, Elliot Lake, ON P5A 1X5 705-848-2287 ext. 2154 bgoulding@city.elliottlake.on.ca	May 2, 2024
		Quote Validity
		7 days
		Quote No.
		Q7407

Terms and Conditions
All payment received over (28 days) is subject to a 2% interest which compounds monthly.

Project info:	
Job Name:	Concrete Core Testing and Footing Depth Measurement
Site Location:	Elliot Lake, ON
GPS Coord:	46.39269404, -82.657191349

Client's approval signature:
Date:
PO#:

Items	Amount
Concrete Sample Retrieval and Testing	\$2,240.00
CPT testing to refusal at the pier footings	\$4,430.00
WRD administration, interpretation and Coordination	\$1,403.00
	TOTAL
	\$8,073.00
One-day site visit during the soil investigation, if required	\$5,076.00

All Prices are Before Taxes

Scope of Work
Scope of work:
1) 4 concrete cores will be obtained. Prior to obtaining the cores, concrete cover meter will be used to avoid encountering reinforcing steel. The cores obtained will be 100 mm in diameter and EXP will endeavor to obtain a minimum core length of 200 mm.
2) CPT test for Eleven (11) pad footings which are present along this part of the structure. CPT cone will be driven as close to the footings as possible at the permissible angle set by the drillers to attempt refusal on the concrete footing. Should the first attempt be unsuccessful no further attempt will be made and the cost noted below would not apply. Should the attempt be successful the procedure will be completed at each pad and the cost below would be invoiced.
More details are in EXP proposal.
Deliverables: Testing report.
Site visits or construction supervision is not included.
Anything not mentioned in the above is considered not included.