



# QUOTE #239

SENT ON:

Dec 30, 2024

**RECIPIENT:**

**City of Elliot Lake**

180 Spruce Avenue  
Elliot Lake, Ontario P5A 2C8

**SENDER:**

**Kennedy Electrical**

131 Frobeld Drive  
Elliot Lake, Ontario P5A 3G7

Phone: 705-849-7751

Email: info@kennedyelectrical.ca

Product/Service	Description	Qty.	Unit Price	Total
Labor	Scope of Work - Removed existing mast, service entrance disconnect and hydro metering cabinet - Install new 600A, 600V 3 phase Eaton switchgear, and make all proper service entrance electrical connections, including proper grounding - Remove all supply wiring for arena, transfer them into new switch gear and terminate onto new breakers - All existing feeder disconnects will now be located in new switch gear and removed from wall - All equipment, panels and electrical in arena will be tested for power - ESA inspection to follow	1	\$10,000.00	\$10,000.00
Materials	- See bill of materials	1	\$65,000.00	\$65,000.00
Notes	- Trenching and digging to be done by others - Any concrete work to be done by others - Duct bank (underground conduit) for electrical to be done by others - Supply conductors from hydro to be supplied by others - All service upgrade materials are included in this quote - ESA inspection cost is included in this quote			

<b>Subtotal</b>	\$75,000.00
<b>HST (13.0%)</b>	\$9,750.00
<b>Total</b>	<b>\$84,750.00</b>

This quote is valid for the next 30 days, after which values may be subject to change.